

	REFURBISHMENT OF CULTURAL CENTER					
Item No	Section No. 1	Unit	Quantity	Rate	Amount	
	Description					
	BILL NO. 1					
	<u>PRELIMINARIES AND GENERALS</u>					
	Establishment of Site and De-Establishment	L Sum				
	<u>REMOVAL OF EXISTING BLINDS</u>					
	<u>Removing of the existing blinds in Boardroom</u>					
1	Blinds 4.25 m x 1.8 m	No	2			
2	Blinds 3.8 m x 1.8 m	No	1			
	<u>REMOVAL OF EXISTING WORK</u>					
	Hacking up / off and removing Floor tiles and disposing of wall tiles including preparing surfaces for new screed, plaster or tile etc. (elsewhere measured)					
3	Floor tiles	m ²	700			
4	Ceramic Tile skirting	m	1000			
	<u>Taking out and removing joinery fittings, etc.</u>					
	<u>Take out and removing glass, etc.</u>					
5	Glass from steel window	m ²	3			
	<u>Taking out and removing mechanical equipment,etc. including disconnection</u>					
6	Air-conditioning units	No	2			
	<u>CLEANING EXISTING SURFACES, ETC</u>					
	Ablution Facilities(Male and Female)					
7	Cleaning to Wall tiling thoroughly with cleaning solutions of a moderately alkali (Cleaning solution to be approved	Sum	1			
	<u>REMEASUREMENT OF ELECTRICAL AND MECHANICAL WORK</u>					
8	Electrical and Mechanical works	Prov Sum	1			R2 000,00
	<u>BUSH CLEARING AROUND PERIMETER OF BUILDING</u>					
9	Clearing of bush,cutting of non vegetative shrubs around the building for a clear working space(3m wide)	Sum	1			
	Carried Forward to Summary of Section No. 1					

REFURBISHMENT OF CULTURAL CENTRE					
Item No	Section No. 2	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 Installing of ironmongery <u>BLINDS</u> <u>Supply, delivery, installation, blinds (Classic Cord – Blue vertical Blind)</u> 1 Blinds 4.25 m x 1.8 m 2 Blinds 3.8 m x 1.8 m <u>SUPPLY AND INSTALLATION OF PROJECTORS AND ELECTRIC PROJECTOR SCREENS, ETC</u> Ceiling Mounted Projector ,1080p (1,920 x 1,080) 3 Maximum WUXGA (1,920 x 1,200) and Electric Projector Screen 84" <u>Supply and Installation of mechanical equipment,etc.</u> Air-conditioning Units, DVMs 4.5 kW VRV/F High Wall Split Unit Power Supply: 1Ph/220-240V/50Hz Mode: Heat Recovery Cooling Capaity: 4.5kW Heating Capaity: 5.0kW Refrigeration Gas: R410A 4 Dimensions: 1,065 x 298 x218mm (WxHxD)				
	Carried Forward to Summary of Section No. 2				

	REFURBISHMENT OF CULTURAL CENTRE				
Item No	Section No. 3	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF PAINTING</u> PAINTWORK ETC TO PREVIOUSLY PAINTED WORK				
	<u>PAINT ON FLOATED PLASTER</u> Clean, prepare and apply one coat professional gypsum and plaster primer or similar approved and two coats acrylic paint				
	1 On internal walls	m2	1200		
	2 On external walls	m2	1000		
	<u>PAINT ON METAL</u> Prepare, sand down and apply Rust Remover Remove rust conerter with clean water and apply Undercoat to bare and repaired areas. Apply two coats Gloss enamel Colour: White				
	3 On windows with burglar bars	m2	150		
	4 On door frames	m2	200		
	Carried Forward to Summary of Section No. 3				

Item No	REFURBISHMENT OF CULTURAL CENTRE				
	Section No. 6	Unit	Quantity	Rate	Amount
	Description				
	BILL NO. 1				
	<u>REMEASUREMENT OF TILING</u>				
	<u>SKIRTING</u>				
	<u>Matt full bodied porcelain tils, size 75x150mm fixed to internal wall plaster.Grou: dark grey</u>				
1	On walls	m	1000		
	<u>600 x 600mm min R9 preferably R10 slip rated Full Bodied Porcelain tiles, mineralised with 3mm grouting lines approved. Natural finish. Grout: light grey or similar approved</u>				
2	On floors	m2	700		
	Carried Forward to Summary of Section No. 6				

	REFURBISHMENT OF CULTURAL CENTRE				
Item No	Section No. 7	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF GLAZING</u> <u>GLAZING TO STEEL WITH PUTTY</u>				
1	Panes exceeding 0,5 m2 and not exceeding 10 m2	m2	10		
Carried Forward to Summary of Section No. 7				R	

REFURBISHMENT OF CULTURAL CENTRE					
Item No	Section No. 8	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF ELETRICAL AND MECHANICAL INSTALLATION</u> <u>Electrical and Mechanical works</u>				
1	Electrical and Mechanical works	Prov Sum			R10 000,00
Carried Forward to Summary of Section No. 8					

	REFURBISHMENT OF CULTURAL CENTRE			
Item No	Section No. 6	Page Number		Amount
Section No	Description			
	BILL NO. 1			
	Final Summary			
	1 Section NO 1- Preliminaries and Generals	1		
	2 Section NO 2- Iron Mongery	2		
	3 Section NO 3- Painting	3		
	4 Section NO 6- Tiling	4		
	5 Section No 7- Glazing	5		
	6 Section No-8 Electrical and Mechanical works	6		
	Sub-Total(A) Add: Contingencies			R10 000,00
	Sub-Total(B) Add: Value Added Tax @ 15%			
	Carried to Form of Tender			