

	BID NO:				
	REFURBISHMENT OF CULTURAL CENTER				
Item No	Section No. 1	Unit	Quantity	Rate	Amount
	Description				
	BILL NO. 1				
	<u>PRELIMINARIES AND GENERALS</u>				
	Establishment of Site and De-Establishment	L Sum			R10 000.00
	<u>REMOVAL OF EXISTING BLINDS</u>				
	<u>Removing of the existing blinds in Boardroom</u>				
1	Blinds 4.25 m x 1.8 m	No	2		
2	Blinds 3.8 m x 1.8 m	No	1		
	<u>REMOVAL OF EXISTING WORK</u>				
	Hacking up / off and removing Floor tiles and disposing of wall tiles including preparing surfaces for new screed, plaster or tile etc. (elsewhere measured)				
3	Floor tiles	m2	700		
4	Ceramic Tile skirting	m	1000		
	<u>Taking out and removing joinery fittings, etc.</u>				
	<u>Take out and removing glass, etc.</u>				
5	Glass from steel window	m2	3		
	<u>Taking out and removing mechanical equipment, etc. including disconnection</u>				
6	Air-conditioning units	No	2		
	<u>CLEANING EXISTING SURFACES, ETC</u>				
	Ablution Facilities(Male and Female)				
7	Cleaning to Wall tiling thoroughly with cleaning solutions of a moderately alkali (Cleaning solution to be approved	Sum	1		
	<u>REMEASUREMENT OF ELECTRICAL AND MECHANICAL WORK</u>				
8	Electrical and Mechanical works	Prov Sum	1		R2 000.00
	<u>BUSH CLEARING AROUND PERIMETER OF BUILDING</u>				
9	Clearing of bush, cutting of non vegetative shrubs around the building for a clear working space(3m wide)	Sum	1		
	Carried Forward to Summary of Section No. 1				

BID NO:					
REFURBISHMENT OF CULTURAL CENTRE					
Item No	Section No. 2	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>Installing of ironmongery</u>				
	<u>BLINDS</u> <u>Supply, delivery, installation, blinds (Classic Cord – Blue vertical Blind)</u>				
1	Blinds 4.25 m x 1.8 m	No	2		
2	Blinds 3.8 m x 1.8 m	No	1		
	<u>SUPPLY AND INSTALLATION OF PROJECTORS AND ELECTRIC PROJECTOR SCREENS, ETC</u> Ceiling Mounted Projector ,1080p (1,920 x 1,080)				
3	Maximum WUXGA (1,920 x 1,200) and Electric Projector Screen 84"	No	1		
	<u>Supply and Installation of mechanical equipment,etc.</u> Air-conditioning Units, DVMs 4.5 kW VRV/F High Wall Split Unit Power Supply: 1Ph/220-240V/50Hz Mode: Heat Recovery Cooling Capaity: 4.5kW Heating Capacity: 5.0kW Refrigeration Gas: R410A				
4	Dimensions: 1,065 x 298 x218mm (WxHxD)	No	2		
Carried Forward to Summary of Section No. 2					

	BID NO:				
	REFURBISHMENT OF CULTURAL CENTRE				
Item No	Section No. 3	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF PAINTING</u> PAINTWORK ETC TO PREVIOUSLY PAINTED WORK				
	<u>PAINT ON FLOATED PLASTER</u> Clean, prepare and apply one coat professional gypsum and plaster primer or similar approved and two coats Plascon low sheen pure acrylic paint. Colour: Prasa neutral. Plascon code: GR-Y03				
1	On internal walls	m2	1200		
2	On external walls	m2	1000		
	<u>PAINT ON METAL</u> <u>Prepare, sand down and apply Plascon Rust Remover (PR1). Remove rust conerter with clean water and apply either Plascon Universal Unsercoat (UC1) or Professional Undercoat (PU800) to bare and repaired areas. Apply two coats Plascon Professional Gloss enamel (PSB 1000). Colour: White</u>				
3	On windows with burglar bars	m2	150		
4	On door frames	m2	200		
	Carried Forward to Summary of Section No. 3				

Item No	BID NO:				
	REFURBISHMENT OF CULTURAL CENTRE				
	Section No. 6	Unit	Quantity	Rate	Amount
	Description				
	BILL NO. 1				
	<u>REMEASUREMENT OF TILING</u>				
	<u>SKIRTING</u>				
	<u>Matt full bodied porcelain tils, size 75x150mm fixed to</u> <u>internal wall plaster.Grou: dark grey</u>				
1	On walls	m	1000		
	<u>600 x 600mm min R9 preferably R10 slip rated Full Bodied</u> <u>Porcelain tiles, mineralised with 3mm</u> <u>grouting lines from Union Tiles or similar</u> <u>approved. Natural finish. Grout: light grey or similar</u> <u>approved</u>				
2	On floors	m2	700		
	Carried Forward to Summary of Section No. 6				

	BID NO: REFURBISHMENT OF CULTURAL CENTRE				
Item No	Section No. 7	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF GLAZING</u> <u>GLAZING TO STEEL WITH PUTTY</u>				
1	Panes exceeding 0,5 m2 and not exceeding 10 m2	m2	10		
Carried Forward to Summary of Section No. 7				R	R0.00

BID NO: REFURBISHMENT OF CULTURAL CENTRE					
Item No	Section No. 8	Unit	Quantity	Rate	Amount
	Description BILL NO. 1 <u>REMEASUREMENT OF ELETRICAL AND MECHANICAL INSTALLATION</u> <u>Electrical and Mechanical works</u>				
1	Electrical and Mechanical works	Prov Sum			R10 000.00
	Carried Forward to Summary of Section No. 8				

	BID NO:			
	REFURBISHMENT OF CULTURAL CENTRE			
Item No	Section No. 6	Page Number		Amount
Section No	Description			
	BILL NO. 1			
	<u>Final Summary</u>			
	1 Section NO 1- Preliminaries and Generals	1		
	2 Section NO 2- Iron Mongery	2		
	3 Section NO 3- Painting	3		
	4 Section NO 6- Tiling	4		
	5 Section No 7- Glazing	5		
	6 Section No-8 Electrical and Mechanical works	6		
	Sub-Total(A)			
	Add: Contingencies			R10 000.00
	Sub-Total(B)			
	Add: Value Added Tax @ 15%			
	Carried to Form of Tender			