

**COMMUNITY SERVICES DEPARTMENT
BUILDING REPAIR AND MAINTENANCE**

SCHEDULE OF QUANTITIES

ITEM No	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	PRELIMLNARIES				
	NOTE: The amount allowed for in preliminaries priced in this section is fixed and will under no circumstances be adjusted				
1.1	Allow for all preliminaries and general responsibilities and obligations under this contract including insurance site establishment and etc	Month	1	10000	10000
2	DOORS				
2.1	Supply and intall 40mm internal doors(masonite), 813 X 2032mm complete with handles, and painting door and frame with white colour	no	6		
2.2	Supply and install 40mm double door hardwood 1511X2032mm high, with two leaves with rebated meeting D2 and flash back including locking systems, and painting doors and frame with white colour	no	1		
2.3	Supply and install of door closer and pushing handles	no	3		
2.4	Supply and install of door shooters	no	3		
2.5	Supply and install of the door handles	no	8		
2.6	Replace and install new of the 1920X850mm strong room door	no	1		
3	WINDOWS				
3.1	Glazing				
	a) 4mm thick clear float glass pane not exceeding	m ²	0.5		
	b) 4mm thick obscure glass pane not exceeding	m ²	0.1		
3.2	Window blinding				
	a) Supply and install of 127mm window blinds	m ²	3.6		
4	BURGLAR DOORS				
4.1	Supply and install of single door 813 X 2032mm wrought iron bugler proof with locking system (frame must be 25mm square tubing with 10mm square bar)	no	2		
4.2	Supply and install of single door 1511 X 2035mm wrought iron bugler proof with locking system (frame must be 25mm square tubing with 10mm square bar)	no	1		
5	FLOOR TILES				
5.1	Remove existing Nyvilon tiles and install of ceramic tiles	m ²	32		
6	WALL PAINTING WORK				
6.1	Two coat acrylic PVA	m ²	83.5		
7	Shelves				
7.1	Supply and install of shelves at store container 6.1x2.3x2.1m high(shelves must be 305x16mm thick shelving board and 400x400mm steel core L brackets)	m ²	20		
8	FENCING				
8.1	Supply and erect concrete palisade fence 30Mpa (Post 3000 longx225mmx140mmm tapered to 80mm, Top and bottom rails 2000mm longx150mmx80mm, Pales 2400 mm longx150mmx80mm and concrete base for post must be 460x460x700mm deep All bolts shall be "electro galvanized")	m	20		
	TOTAL CARRIED FORWARD				10 000.00