SHEDULE OF QUANTITIES FOR LEDWABA CEMETRY REPAIR WORK

ITEM No	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
1	PrelimInaries				
	NOTE				
	The amountallowed for in preliminaries priced in this section fixed and will under no circumstances be adjusted				
1.1	Allow for all preliminaries and general responsibilities and obligations under this contract including insurance site establishment and etc	Month	1	5000	5000
2	Roof				
2.1	Repair the roof tiles	sum	1		
3	Repair of damaged waste water disposal system				
3.1	Excavation of 2.5mØX3.5m deep treanch for new Septic tank	m³	17.2		
3.2	Supply and install of 2500litres of PVC Septic tank in the treanch and 300x300mm concrete topping cap above the ground. Backfilling to trenches compacted to 93% Mod.AASHTO in leyers	no	1		
3.3	Decommession of existing	sum	1		
4	Toilet				
4.1	Remove and inset Complete WC conecting to existing services	no	2		
4.2	Repair of Urinal	sum	1		
4.3	Repair of basin tap	sum	1		
5	Burglar door				
5.1	Repair of burglar door hinge(welding)	sum	1		
6	Door				
6.1	Supply and install of door shooters and block plates	no	7		
7	Electricity instalations				
7.1	Supply and install of porcelian bowl fitting lamps, globes and commissioning	no	4		
7.2	Single lever switch	no	5		
	TOTAL CARRIED TO SUMMARY				

SUMMARY OF SCHEDULES OF QUANTITIES

SECTION	DESCRIPTION	AMOUNT
1	SECTION 1: PRILEMINARY	
2	SECTION 2: BUILDING STRUCTURAL ELEMENTS	
	SUBTOTAL	
	VAT 14%	
	TOTAL	