

**LEBOWAKGOMO LIBRARY**  
**BUILDING REPAIR AND MAINTENANCE**

**SCHEDULE OF QUANTITIES**

Item No	Description	Unit	Quantity	Rate	Amount
<b>1</b>	<b>PRELIMINARIES</b>				
	NOTE:				
	The amount allowed for in preliminaries priced in this section is fixed and will under no circumstances be adjusted				
1.1	Allow for all preliminaries and general responsibilities and obligations under this contract including insurance site establishment, cleaning and etc	sum	1	5000	5000
<b>2</b>	<b>Construction of 1500x1500mm shower rooms with brick structure, walls tiles</b>				
	Relocation of the existing wash basin, erect on other site of the wall and wall tiling 500x500mm on the wall	sum	1		
	Demolition of existing wall and concrete slab	m <sup>2</sup>	0.5		
	Brickwork of NFP one brick wall and plastering	m <sup>2</sup>	30		
	25Mpa/19mm concrete for floor slab	m <sup>3</sup>	0.5		
	Painting one under coat and two coat acrylic PVA on wall to fit existing	m <sup>2</sup>	15		
	200x200x8mm gloss white glazed grade1 ceramic tile fixed with adhesive to plaster and with joining compound on wall in isolated panel basin	m <sup>2</sup>	60		
	350x350x11mm thick, fixed to floor with approved cement based adhesive. White edge trim at edges and cornes fixed simultaneously with tiles and cut tile skirting 75mm high	m <sup>2</sup>	70		
	800x200mm patterned glass sliding shower door	no	2		
<b>3</b>	<b>Plumbing</b>				
	Shower mixer and fittings	no	2		
	22mm Copper pipe and fittings	m	15		
	plumbing connection	Sum	1		
<b>4</b>	<b>Door</b>				
	Locking system and Handles	no	6		
<b>5</b>	<b>Additional</b>				
	Supply and installation of Lockerble toilet roll holder	no	7		
	Supply and installation of 300x500mm Mirror	no	1		
	Cleaning of the existing toilets seats, basin and stainless steel Male Urinals with chemical	Sum	1		
<b>TOTAL CARRIED FORWARD</b>					

**LEBOWAKGOMO LIBRARY**

**BUILDING REPAIR AND MAINTENANCE**

**SUMMARY OF SCHEDULES OF QUANTITIES**

DISCRIPTION	AMOUNT
SECTION A: BUILDING STRUCTURAL ELEMENTS	
SUBTOTAL	
VAT 14%	
TOTAL	