

CALCULATION OF TENDER AMOUNT

SUMMARY OF SCHEDULE OF QUANTITIES

<u>SCHEDULE A : PERIMETER FENCE</u>				Total To Date
TOTAL SCHEDULE A : FENCE		R		
	<u>Sub-Total</u>	R		
	14% VAT	R		
TENDER SUM CARRIED TO FORM OF TENDER		R		

SIGNED ON BEHALF OF TENDERER :

PERIMETER FENCE - BILL OF QUANTITIES

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	CONSTRUCTION OF 447m PERIMETER FENCE AT MAGATLE TRAFFIC STATION				
1	Clearing and grubbing of vegetation along the fence line	m ²	894		
2	Excavation of 400x400x500mm deep hole	m ³	4		
3	Backfilling with Class 15/19 concrete for all corner posts & stays	m ³	4		
4	supply & install 2.4mx76mm Steel silver post	No	11		
5	supply & install 2.4m x 38mm steel stay complete with bolt and nuts	No	18		
6	Supply & install 1.8m 360mm x 360mm.52KP Jpeg China galvanised razor wire	m	447		
7	Supply & install 2.4m fence drobers	No	70		
8	Supply & install 2.4mm x 1300m binding wire	No	2		
9	supply & install 4mm x 1500m galvanised wire	m	1 500		
10	supply & install 3m x 2.4 galvanised steel sliding gate complete	No	1		
11	Supply & install 6m x 2.4 galvanised steel sliding gate complete	No	1		
TOTAL CARRIED FORWARD TO SUMMARY					