

**SECTION A: MAMAOLO COMMUNITY HALL
REFURBISHMENT
SECTION 1: INSIDE AND OUTSIDE WORKS ON THE
COMMUNITY HALL
INSTALLATION 1: BUILDING STRUCTURAL ELEMENTS**

Item No	Description	Unit	BILL Qty	Rate	Amount
1	PRELIMINARIES				
	NOTE:				
	The amount allowed for in preliminaries priced in this section is fixed and will under no circumstances be adjusted				
1.1	Allow for all preliminaries and general responsibilities and obligations under this contract including insurance site establishment and etc	month	1	R 10 000.00	R 10 000.00
2	Carpentry and Joinery				
2.1	40mm double door 1511x2023mm high,with two equal leaves with 8 panels with rebted meeting stiles D2 including locking systems	no	5		
2.1.1	Apply and paint clear vanish coating on doors or similar approved paint	no	6		
	supply and installation of skirting	m	35		
3	Plumbing and drainage				
3.1	22mm class O copper pipe capillary coupling	m	10		
3.2	protea semi closed coupled white vitreous china WC suite comprising 90 outlet open rim washdown pan and 9 litre low level cistem complete with heavy duty double flap toilet seat (complate) or similar	no	4		
3.3	455x290mm batam white viteous china cloakroom basin with two taps whole including intergrated overflow and chainstay hole,bolted to wall wiyh 10mm bolts including taps(Complete) or similar	no	6		
4	Glazing				
4.1	Replace and install 3mm class window pane glass exceeding .5m2 not exceeding 1 m2	m ²	1		
4.2	Supply and install window stays	no	15		
5	Fencing				
	double gate 6.0x 1.8 high formed of 50mm diametre and 2.5mm galvanised steel pipe outer frame and diagonal brace welded onto gate frame and with boom as locking system	no	1		
6	Bugler doors				
6.1	supply and installation of single door 09x2.5wrought iron bugler proof with locking system (frame must be 25mm square turebing with 10mm round bar)	no	3		
6.2	supply and installation of double door 1511x2035 wrought iron bugler with locking system(frame must be 25mm square turebing with 10mm round bar)	no	5		
TOTAL CARRIED TO SUMMARY					

SECTION A: MAMAOLO COMMUNITY HALL REFURBISHMENT SECTION 2: INSIDE AND OUTSIDE WORKS ON THE COMMUNITY HALL INSTALLATION 1: ELECTRICAL ELEMENTS					
Item No	Description	Unit	BILL Qty	Rate	Amount
7	Electrical repairs and maintenance				
	Supply and install the following				
7.1	1.5 x fluorescent tubes	m	12		
7.2	1.5 x fluorescent fittings	no	4		
7.3	single lever switch cover (crabtree)	no	5		
7.4	double switch covers (crabtree)	no	3		
7.5	40A stove isolator cover (crabtree)	no	1		
7.6	25A double pole geyser circuit breaker	no	1		
7.7	50Ax5KA three pole isolator	no	1		
7.8	63Ax5KA double pole isolator	no	1		
7.9	63Ax5KA earth leakage	no	3		
7.1	20Ax5KA geyser circuit breaker	no	12		
7.11	10Ax5KA circuit breaker	no	8		
7.12	sockets outlets and cover (crabtree)	no	5		
7.13	125w x decorative post top luminaire range (bekaray)	no	6		
7.14	125w x MV globes	no	6		
7.15	2.5mm x 3 core suffix cable	no	100m		
7.16	300mm x porcelain bowl fitting lamps	no	2		
7.17	s300sa nema base roysethomson electronic photocell complete set	no	4		
TOTAL CARRIED TO SUMMARY					

SECTION A: MAMAOLO COMMUNITY HALL
 REFURBISHMENT
 SECTION 3: INSIDE AND OUTSIDE WORKS ON THE
 COMMUNITY HALL
 INSTALLATION 1: SUMMARY

INSTALLATION 1: BUILDING STRUCTURAL ELEMENTS	R
INSTALLATION 1: ELECTRICAL ELEMENTS	R
SUBTOTAL	R
VAT 14%	R
TOTAL	R

NB : TOTAL AMOUNT CARRIED TO FORM OF OFFER